ROADSENSE | Infrastructure Intelligence

DATE: November 10, 2026
STANDARDS: ASTM D6433 | IRC:SP:77 / IRC:82

ASTM D6433 CONDITION	ROUGHNESS INDEX (IRI)	MATERIAL REQUIRED	ESTIMATED REPAIR BUDGET
10.0 / 100 **Serious / Failed**	**24.84** m/km ASTM E1926	**9461.5 kg** Cold-Mix Bitumen	**Rs. 475929** ($7904.63)

Hazard Classification & Severity Breakdown

Hazard Category	Impact Severity	Count	Recommended Municipal Action
Pothole	Severe (Z >= 3.0)	94	Immediate Cold Patching / Asphalt Mill & Infill (<48h)
Pothole	Moderate (Z 2.0-3.0)	27	Scheduled Maintenance (<14 days)
Pothole	Minor / Anomaly (Z < 2.0)	46	Surface Seal Coating / Monitor
Speedbreaker	Standard Deflection	12	Verify Regulatory Height & Signage Painting

Priority Maintenance Dispatch Table (Top Critical Hazards)

#01	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91864, 77.55448	2551cm² depth 12.0cm	**36.0 kg**	Rs.1918	Deep milling, granular sub-base recompaction & DBM overlay
#02	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91769, 77.55307	2399cm² depth 12.0cm	**33.8 kg**	Rs.1823	Deep milling, granular sub-base recompaction & DBM overlay
#03	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91862, 77.55452	1823cm² depth 12.0cm	**25.7 kg**	Rs.1457	Deep milling, granular sub-base recompaction & DBM overlay
#04	**Speedbreaker** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91775, 77.55431	1435cm² depth 12.0cm	**20.2 kg**	Rs.1210	Deep milling, granular sub-base recompaction & DBM overlay

#05	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91773, 77.55419	25000cm² depth 7.1cm	**99.9 kg**	Rs.4795	Deep milling, granular sub-base recompaction & DBM overlay
#06	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91776, 77.55258	1274cm² depth 11.7cm	**17.5 kg**	Rs.1089	Deep milling, granular sub-base recompaction & DBM overlay
#07	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91813, 77.55267	25000cm² depth 6.8cm	**99.9 kg**	Rs.4795	Deep milling, granular sub-base recompaction & DBM overlay
#08	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91813, 77.55267	1238cm² depth 11.4cm	**16.6 kg**	Rs.1047	Deep milling, granular sub-base recompaction & DBM overlay
#09	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91773, 77.55275	1219cm² depth 11.2cm	**16.0 kg**	Rs.1021	Deep milling, granular sub-base recompaction & DBM overlay
#10	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91788, 77.55372	1118cm² depth 10.2cm	**13.4 kg**	Rs.903	Deep milling, granular sub-base recompaction & DBM overlay
#11	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91792, 77.55350	1064cm² depth 9.8cm	**12.2 kg**	Rs.851	Deep milling, granular sub-base recompaction & DBM overlay
#12	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91870, 77.55452	25000cm² depth 6.2cm	**99.9 kg**	Rs.4795	Deep milling, granular sub-base recompaction & DBM overlay

Camera Ground-Truth Evidence (AI Detection Bounding Boxes)

Visual verification frames captured by vehicle optical sensors at timestamp of impact.




Pothole: 73%


Pothole: 88%


Pothole: 63%