ROADSENSE | Infrastructure Intelligence

DATE: November 10, 2026
STANDARDS: ASTM D6433 | IRC:SP:77 / IRC:82

ASTM D6433 CONDITION	ROUGHNESS INDEX (IRI)	MATERIAL REQUIRED	ESTIMATED REPAIR BUDGET
10.0 / 100 **Serious / Failed**	**19.55** m/km ASTM E1926	**6736.8 kg** Cold-Mix Bitumen	**Rs. 326878** ($5183.72)

Hazard Classification & Severity Breakdown

Hazard Category	Impact Severity	Count	Recommended Municipal Action
Pothole	Severe (Z >= 3.0)	53	Immediate Cold Patching / Asphalt Mill & Infill (<48h)
Pothole	Moderate (Z 2.0-3.0)	14	Scheduled Maintenance (<14 days)
Pothole	Minor / Anomaly (Z < 2.0)	12	Surface Seal Coating / Monitor
Speedbreaker	Standard Deflection	0	Verify Regulatory Height & Signage Painting

Priority Maintenance Dispatch Table (Top Critical Hazards)

#01	**Pothole** Moderate	**Cat Category B (Standard Pothole Cavity)** IRC:SP:77-Clause 4.1	12.91578, 77.55251	5515cm² depth 3.4cm	**22.0 kg**	Rs.1292	Square cut, edge priming & Cold-Mix Bituminous Patching
#02	**Pothole** Moderate	**Cat Category B (Standard Pothole Cavity)** IRC:SP:77-Clause 4.1	12.91578, 77.55251	5515cm² depth 3.4cm	**22.0 kg**	Rs.1292	Square cut, edge priming & Cold-Mix Bituminous Patching
#03	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91569, 77.55232	25000cm² depth 3.4cm	**99.9 kg**	Rs.4795	Deep milling, granular sub-base recompaction & DBM overlay
#04	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91565, 77.55233	25000cm² depth 3.4cm	**99.9 kg**	Rs.4795	Deep milling, granular sub-base recompaction & DBM overlay

#05	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91565, 77.55233	25000cm² depth 3.4cm	**99.9 kg**	Rs.4795	Deep milling, granular sub-base recompaction & DBM overlay
#06	**Pothole** Low	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91565, 77.55231	15708cm² depth 3.4cm	**62.7 kg**	Rs.3123	Deep milling, granular sub-base recompaction & DBM overlay
#07	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91565, 77.55234	25000cm² depth 3.4cm	**99.9 kg**	Rs.4795	Deep milling, granular sub-base recompaction & DBM overlay
#08	**Pothole** Moderate	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91572, 77.55242	21007cm² depth 3.4cm	**83.9 kg**	Rs.4076	Deep milling, granular sub-base recompaction & DBM overlay
#09	**Pothole** Moderate	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91577, 77.55245	21007cm² depth 3.4cm	**83.9 kg**	Rs.4076	Deep milling, granular sub-base recompaction & DBM overlay
#10	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91590, 77.55252	25000cm² depth 3.4cm	**99.9 kg**	Rs.4795	Deep milling, granular sub-base recompaction & DBM overlay
#11	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91590, 77.55252	25000cm² depth 3.4cm	**99.9 kg**	Rs.4795	Deep milling, granular sub-base recompaction & DBM overlay
#12	**Pothole** Severe	**Cat Category C (Structural Base / Sub-base Failure)** IRC:82-Clause 6.4	12.91590, 77.55252	25000cm² depth 3.4cm	**99.9 kg**	Rs.4795	Deep milling, granular sub-base recompaction & DBM overlay

Camera Ground-Truth Evidence (AI Detection Bounding Boxes)

Visual verification frames captured by vehicle optical sensors at timestamp of impact.


Pothole: 54%


Pothole: 89%


Pothole: 40%


Pothole: 89%